

MGS Mass Properties 5/15/96

Jim Taylor



May 8-9 Spin Test for Mass Properties



1. Weigh Spacecraft

Minimum Non-Flight Hardware (Configured for Acoustics) IPA Loaded (95% all Tanks) Develop "Puts and Takes" List

- 2. Measure Center of Gravity

 Three Locations Achieved With Ballast
- 3. Measure Products of Inertia

 Two Measurements with Different Center of Gravity
- 4. Measure Z-Axis Moment of Inertia
- 5. Conduct Spacecraft Magnetics Survey
- 6. Measure Spacecraft Launch Envelope



Spacecraft Mass (5/15/96)



MGS Spacecraft Weight Analysis				
Latest Measurement May 9, 1996	CBE	CBE+Growth	CBE - ∆V (20.7mps)	CBE + Growth · ΔV (20.7mps)
Installed Items (MEL)	587.08	587.59	587.08	587.59
Correction to MEL	0.67	0.67	0.67	0.67
Flight Items to Be Added (Estimated)	38.39	42.98	38.39	42.98
Flight Items to Be Added (Weighed)	43.45	43.97	43.45	43.97
Total S/C CBE Dry Mass, kg	668.92	674.54	668.92	674.54
Total S/C CBE Wet Mass, kg	1053.76	1062.60	1044.68	1053.44
Fuel,kg	233.57	235.53	227.20	229.11
Fuel Margin, KG	1.27	-0.69	7.65	5.74
Fuel Margin, % (Negative Means Over Fill)	0.54%	-0.29%	3.37%	2.51%
Oxidizer, kg	151.26	152.53	148.55	149.80
Oxidizer Margin, kg	16.96	15.69	19.67	18.43
Oxidizer Margin, % (Negative Means Over Fill)	11.22%	10.29%	13.24%	12.30%
Total Propellant Loaded	384.83	388.06	375.75	378.90
Total Growth Mass		5.10		5.10
Growth Mass Installed Items		0.51		0.51
Growth Mass NOT Installed Items		4.59		4.59



Δ V's and Burn Times (Budget)



MEA ISP, sec =	317.00			Wet Mass, kg	1053.76
MEA, Blowdown Isp=	315.00			_	
ACS ISP, sec =	220.00				
ACS, pulse Isp=	190.00				
Engine Mass Flow, kg/sec	0.21				
	$\Delta V, m/sec$	$\Delta V, m/sec$	Post Burn	Burn Time,sec	Burn Time,sec
Maneuver	Monoprop	Biprop	S/C Mass,kg	ACS	Main Engine
TCM 1,2	0.30	49.90	1036.82	18.33	79.69
TCM 3,4	3.00	0.00	1035.38	180.09	0.00
MOI	5.90	975.60	753.67	353.45	1323.61
Aerobraking Walk-in	2.60	8.00	750.81	113.46	9.25
Aerobraking Main Phase	5.00	0.00	749.07	217.25	0.00
Aerobrake Main Phase	5.00	0.00	747.07	250.93	0.00
Aero Walk-ou:t:Trans	20.00	0.00	740.17	861.68	0.00
Aero Walk-out: Rot	30.00	0.00	728.35	1477.74	0.00
TransMap-ABX	0.40	60.20	714.25	16.88	66.30
TransMap-TMO	0.10	16.10	710.52	4.14	17.51
Aerobrake Pop-Up	2.50	14.50	706.37	102.86	15.79
V Reserves	2.00	10.70	703.28	81.81	11.59
Mapping-OTM	3.90	7.50	700.30	158.77	8.09
Mapping-ACS	40.00	0.00	685.43	1859.21	0.00
Quarantine Orbit	12.00	0.00	681.63	475.23	0.00
Relay-OTM	4.80	0.00	680.11	189.35	0.00
Relay-ACS	10.00	0.00	676.47	455.04	0.00
TOTALS	147.50	1142.50		6816.21	1531.84
TOTAL V, m/sec	1290.00				
TOTAL PROP, kg:	384.83				
ALLOW. DRY MASS, kg	668.92			<u> </u>	

	ΔV,m/sec	ΔV,m/sec
Maneuver	Monoprop	Biprop
TCM 1,2	0.30	42.00
TCM 3,4	3.00	0.00
MOI	5.90	975.60
Aerobraking Walk-in	2.60	8.00
Aerobraking Main Phase	5.00	0.00
Aerobrake Main Phase	5.00	0.00
Aero Walk-ou:t:Trans	20.00	0.00
Aero Walk-out: Rot	30.00	0.00
TransMap-ABX	0.40	60.20
TransMap-TMO	0.10	16.10
Aerobrake Pop-Up	2.50	14.50
V Reserves	2.00	5.60
Mapping-OTM	3.90	7.50
Mapping-ACS	40.00	0.00
Quarantine Orbit	17.00	0.00
Relay-OTM	0.70	0.00
Relay-ACS	1.40	0.00
TOTALS	139.80	1129.50
TOTAL V, m/sec	1269.30	









Item	Percent Growth
Ballast	100.00%
MLI	20.00%
Radome	10.00%
NSI's	10.00%
Coatings, Paint, Teflon	10.00%
MLI Ground Straps	5.00%
Connector Covers	5.00%
Flight Batteries	1.00%
Main Enable Plug	1.00%
MOLA	1.00%
TES	1.00%
Installed and Weighed Equipment	0.10%



Accuracy Of Measurements



Load Cell
$$\pm 0.25\%$$
 of Lift-Tare = ± 2.39 kg

IPA Loaded Fuel =
$$\pm$$
 .45 kg

$$= \pm 2.4 \text{ kg}$$

IPA Loaded Oxidizer =
$$\pm$$
.23 kg

$$= \pm 1.8 \text{ kg}$$





Mass (Kg)	Mass (Kg)	Comments
Weighed	Estimated	
359.87	9.19	369.06
		NOTE: Bubble Wrap 5.91 Grams/Ft2; Plastic Wrap = 5.68 grams/Ft2; Pink Poly = 6.72 grams/Ft2; Kapton Tape= 1.56 Grams/Ft.; Purge Line = XXX Grams/Ft.,Red Tag = 9 grams each
0.05	0.16	
0.05		Weighed 2/26 (26.7 grams each including screws)
	0.02	,
	0.02	
	0.02	Est 3 sq ft
	0.01	
	0.01	
	0.02	
	0.06	Est at 10 grams @
	0.01	
	Weighed 359.87 0.05	Weighed 359.87 Estimated 9.19 0.05 0.16 0.05 0.02 0.02 0.02 0.02 0.01 0.01 0.02 0.06





Propulsion Module	0.05	0.15	
-X Side			
Plastic on He Tank		0.02	Est 3 sq ft
2 Red Tags		0.02	
-Y Side			
Dust Cover		0.01	On Electrical Tower Below Deck
2 Red Tags		0.02	
2 MAG Hazard Labels		0.01	
+X Side			
2 SSD Covers	0.05		weighed 2/26
70 inches Tape		0.01	
+Y Side			
Dust Cover		0.01	On Electrical Tower Below Deck
100 inches Tape		0.01	
4 Red Tags		0.04	
2 Non Conformance Stickers		0.00	





Nadir Equipment Deck	46.32	0.37	
MOC Soft Cover		0.10	Weighed 4/18
ER Cover	0.11		Weighed at Vendor
CSA Cover	0.16		Weighed 5/14/96 at 5.63 Oz
4 MHSA Lens Covers	0.28		70 grams each
2 SSD Covers	0.05		26.7 gram each
MR 50 OHM Load Resistor		0.05	Greg H. Estimate
2 MR Connector Savers		0.01	Greg H. Estimate (10 grams @)
MOLA Mass Simulator	26.99		This is flight weight
25 feet of purge line		0.20	
MOLA Lifting Lugs	0.46		Weighed 5/14/96 at 16.07 Oz.
TES Mass Simulator	14.70		
Kapton Tape (100 inches)		0.01	
S/C Lifting Lugs	3.57		



	Mars	,
	Global	1
5	Surveyo	r

High Gain Antenna	0.00	0.00	
Solar Arrays	0.11	0.00	
4 SSD Covers	0.11		2 on each panel 26.7 gram each
Other Equipment	313.47	8.52	
28 NSI Simulators	0.33		
Thruster Nozzle Caps and Foam	0.03		2.5 grams each
2 Battery High Side Enable Tool Was NOT Installed			Weighed by Zercher (956 grams each)
2 Test Batteries	26.53		Weighed
Fuel Tanks Referee Fluid (IPA)	181.22		Estimated Loading Accuracy ± 1 pound
Ox Tank Referee Fluid (IPA) NED Witness Plate	90.50 0.80		Estimated Loading Accuracy ± 0.5 pound
Ballast	3.64		
1 Ballast Bracket Thermal Clip & Screws	0.03		
Accels Wires (41)	7.37		
Blocks for Accel Mount (37)	1.74		
Accels (41-302's & 6-306's))	1.29		
Thermocouples, Wire, Connectors (261 +66)		8.52	

Systems Engineering

Install Before Flight Items (5/15/96)



I t e m	Mass (Kg)	Comments			
Total of All Items	81.85	Estimated=			
		Weighed=	43.45		
Equipment Module	1.46	Comments		_	
*6 MLI Blankets & Straps	1.46	Est.		_	
				_	
Propulsion Module	34.35				
*38 MLI Blankets & Straps	3.93	Est.		_	
4 Ballast Bracket Thermal Clips & Screws	0.12	30.8 gs @		High Gain Antenna	1.54
28 NSIs	0.33				
Flight Batteries	26.53	Est.		*26 MLI Blankets & Straps	1.43
Ballast	2.00	Est. Nominal Value		HGA Radome	0.11
Pressurant (He)	1.43				
				Solar Arrays	0.75
Nadir Equipment Deck	43.48				
				*26 MLI Blankets & Straps	0.75
MOLA (w/Attach H/W)	26.99				
TES	14.70				
MR J6 D/A Connector Cover	0.01				
MAG J6 D/A Connector Cover	0.01			Thermal (Other)	0.27
ER High Voltage Enable Plug	0.01				
*17 MLI Blankets & Straps	1.76	Est.		20 closeout blankets	0.27



Spin Test Results (5/9/96)



Measured Values		Spacecraft Values	
Xcg	Ycg	Xcg	Ycg
0.0690	-0.1415		
lxz	lyz	lxz	lyz
Izz	Principal Axis	Izz	Principal Axis
	Add Ballast		
+ X , + Y	- X , + Y	- X , - Y	+ X , - Y
	1.94 kg		
Measured Values		Spacecraft Values	
Xcg	Ycg	Xcg	Ycg
0.0024	-0.0673		
lxz	lyz	lxz	l y z
-15241	-3367		
Izz	Principal Axis	Izz	Principal Axis
	Add Ballast		
+ X , + Y	- X , + Y	- X , - Y	+ X , - Y
	3.635 kg		
Manager I Malana		0	
Measured Values		Spacecraft Values	
Xcg	Ycg	Xcg	Ycg
-0.0533	-0.0016	_	
Ixz	lyz	Ixz	lyz
-16825	-490	 	
Izz	Principal Axis	Izz	Principal Axis
1302011			

Ballast Requirements

C.G. \leq .13 cm Principal Axis \leq 1 deg.

	+ X , + Y	- X , + Y	- X , - Y	+ X , - Y
TOP				
ВОТ				



Preliminary Launch Envelope Verification



- •HGA and Solar Arrays Will Be Deployed During ATLO Testing
- Solar Arrays Will Be Removed For Shipping to KSC
- Thermal Blankets Not Installed
- •Repeatability of Installation Expected to Be Very Good (±0.010 inch)
- Spacecraft Rotation Facilitated By Spin Table Air Bearing Rotated (Manual) To Proper Positions - Then Locked Down For Measurements
 - •No Immediate Issues. MDAC Reviewing the Numbers

Measurement Point	Mission Specification	Measure	Difference
HGA Strut	50.900	50.920	0.020
HGA Strut	51.200	51.250	0.050
HGA Dish Edge	51.100	51.150	0.050
Solar Array +X,+Y	49.20	49.240	0.040
Solar Array +X,-Y (RTV	49.20	49.560	0.360
Solar Array -X,-Y (Wir	49.20	49.330	0.130
Solar Array -X,+Y (Wir	49.20	49.560	0.360
Ballast (-X,+Y)	49.80	49.580	-0.220

Nominal Envelope Radius=50 inches



Systems Engineering

Spacecraft Magnetics Survey



Two Magnatometers Located at Solar Array Gimbal Elevation at Distances Of 3 feet and 5 feet from solar array

Spacecraft Rotated Approximately 5 RPM for 10 (+) Revs CW and 10 (+) Revs CCW

Technique gave an excellent magnetic signature of the spacecraft.

Results show a dipole that is slightly out of spec. Most likely source is the TWTA assembly.

MAG PI is continuing to analyze the data to determine if corrective action is required.



Things To Do



- 1. Update Spacecraft Mass Properties Math Model
- 2. Determine Spacecraft Ballast Requirements (Preliminary)
- 3. Determine MOI's for Mapping Orbit to Get Momentum Unload ΔV Update
- 4. Next Spin Test After Thermal Vac (July 23)
- 5. Last Spin Test at KSC
 Spin Table Setup
 Wet or Dry?
 KSC Safety Requirements



Launch Safe Mode & DSN Acquisition Time Available



A Discovery (During ATLO Testing) - Safe Mode Monitors Bus Current - Instead Of the Intended Total of Solar Array Current and Bus Load.

Safe Mode Turns Off The TWTA For 2 Hours (Then On For 2 Hours) If Insufficient Current. Helps Prevent Damage to The Batteries If No Sun on The Arrays.

- Designed for Eclipse Detection
- Also Works Great for Aerobrake
- Also Works (Needed) If Solar Arrays Did Not Deploy Properly



Launch Safe Mode & DSN Acquisition Time Available



The Problem:

During Launch The Bus Current From The Box Loads <u>Plus</u> The Solar Array Charge Current Is Sufficient For Safe Mode To Leave The TWTA ON.

However, The Batteries Will Be Re-Charged in About 1 Hour And the 7.5 Amps Charge Current Goes to Zero. The Remaining Current Is Not Sufficient For The Safe Mode Monitor to Leave The TWTA Turned On.



Launch Safe Mode & DSN Acquisition Time Available



Solutions:

- 1. Install a Software Patch To Turn the TWTA On if Safe Mode Entered During Launch and Leave it On.
 - a) Works Only If Memory Not Scrambled
 - b) Memory Lost If Safe Mode Entered Do to POR
- 2. Install Hardware Fix to Make Safe Mode Monitor the Solar Array Current (Including the Current Dumped to the PSA's)
 - a) Hardware is Being Designed and Will Be Ready for Installation When an Opportunity Arises.
 - b) Requires Opening the EM And NOBODY Wants to Do That Because of Completed ATLO Testing.
 - 3. Prepare Emergency Ground Command To Turn TWTA On
 - a) Need Initial Acquisition To Know That It Is OK To Turn TWTA On (Do We Really Have Power on The Arrays?)

